BRUHAT BANGALORE MAHANAGARA PALIKE

DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division

Modified SCHDULE-B

Name of Work: Improvements and Construction of CC Roads at Kempegowda nagara 2nd & 3rd Main 4th 6th B & 6th C Cross & North side of the Ganesha Saw Mill road & Other Cross roads in Dasarahalli ward No:15

Sl	Description of Work	Unit	Qty	Sanctioned Rates	
				In figures (Rs)	In Words (Rs)
1	2	3	4.00	5	6
1	Earthwork excavation by manual means in ordinary soil involving an avegage horizontal throw up to 2 meters and an average lift up to 0.5 m, excavated surface leveled and sides neatly dressed the diposed earth to be levelled neatly after breaking of clods complete as per specifications	Cum	188.40	74.59	Rupees Seventy Four and Fifty nine Paise Only
2	Vaccum de-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator, HOM of Machinery, screed Vibratory, Power Floater, blade and disc etc., with all lead and lift	Sqm	292.68	81.87	Rupees Eighty one & Eighty seven Paise Only
3	Providing Concrete Groove cutting for width of 5mm to 10mm and depth 80mm100mm including cost of cutting machine generator & HOM of machinery, including cost of blade coolant etc., including cleaning of groove & Providing sand and hot bitumen fillars, and fillars metal etc., including cost of conveyance of all materials, labour lead and lift charges and all other incidental charges as per drawing and as per specifications.	rmt	126.00	104.61	Rupees One Hundread four & Sixty One paise Only
4	Earthwork excavation for foundation of buildings, water supply, sanitary, lines and electrical conduits either in pits or in trenches 1.5 m and above in width, in hard soil not exceeding 1.5m. in depth including dressing the bottom and and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead up to 50 m. after breaking of clods complete as per specifications.	Cum	236.16	239.45	Rupees Two Hundread Thirty nine and Forty five Paise Only
5	Removing B.S.Slab of drain and stacking etc., complete Qty Executed upto 125%	Sqm	136.00	52.91	Rupees Fifty two & Ninety one Paise Only
6	Refixing stone slabs of drains and pointing in CM 1:3 etc complete Qty Executed upto 125%	Sqm	81.60	65.47	Rupees Sixty five & Forty Seven Paise Only

EXECUTIVE ENGINEER
Bruhat Bangalore Mahanaga
Dasarahalli Division, Bangalore-73.

7	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @180 kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Qty Executed upto 125%	Cum	96.69	4210.63	Rupees Four Thousand two Hundread ten & Sixty three Paise Only
	Qty Executed above 125%		8.38	4427.47	Rupees Four Thousand Four Hundread twenty seven & Forty seven Paise Only
8	Cement Concrete Pavement :- Construction of un-reinforced, dowel jointed, plain cement concrete pavement over a prepared sub base with 43 grade cement design mix M30 at 360 kg per cum, with 25mm and down size graded granite metal coarse aggregate at 0.69 cum and fine aggregates @ 0.46 cum with superplastizer at 3lts conforming to IS 9103-1999 reaffirmed 2008. coarse and fine aggregate conforming to IS:383, mixed in a batching and mixing plant as per approved mix design, transported to site, laid with a fixed form or slip form paver, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, dowel bar, tie rod, admixtures as approved, curing, compound, finishing to lines and grades as per drawing complete as per specifications.	Cum	288.14	5765.73	Rupees Five Thousand Seven Hundread Sixty five & Seventy three Paise Only
9	Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69cum and fine aggregates @ 0.43cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost all materials, labour, HOM of machinery, curing complete as per specifications. Qty Executed upto 125%	Cum	51.56	4800.00	Rupees Four Thousand eight Hundread Only
	Qty Executed above 125%		20.02	5041.51	Rupees Four Thousand Forty one& Fifty one Paise Only
10	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness above 200 mm including cost of all materials, labour complete as per specifications. Qty Executed upto 125%	Sqm	517.50	335.42	Rupees Three Hundread Thirty five and Forty twoPaise Only
	Qty Executed above 125%		76.50	284.73	Rupees Two Hundread eighty four and Seventy three Paise Only

EXECUTIVE ENGINEER
Bruhat Bangalore Mahanagara [illegible]ke
Dasarahalli Division, Bangalore-57

11	Providing T.M.T. steel reinforcement for R.C.C. work including straightening cutting, bending, hooking, placing in position, lapping and (or welding wherever required, trying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications	ton	13.66	58551.47	Rupees Fifty Eight Thousand Five Hundread Fifty one & Forty Seven Paise Only
12	Supplying and fixing precast rainforced concrete slab 10cm thick including cost of reinforcement as pwe design and drawing materials cost, tranportion hire charges of machinary, machine cutting the verticale face to get plain even surface ctc. Complete with all leads and lift convetyenc charges labour charges inclusive cost of all materials Qty Executed upto 125%	Sqm	168.75	1328.64	Rupees One Thousand three Hundread Twenty eight & Sixty four Paise Only
	Qty Executed above 125%		11.25	1373.12	Rupees One Thousand three Hundread Seventy three & Twelve Paise Only
13	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km Qty Executed upto125%	Cum	264.26	64.96	Rupees Sixty four & Ninety Six Paise Only
	Qty Executed above 125%		160.30	69.34	Rupees Sixty nine & Thirty four Paise Only

Signature of the Contractor

Executive Engineer
Dasarahalli Division